
## M4/PIR/STEEL





### M4 antiwater – PIR – C Steel

### Installation - Design:

- Must follow, the M-Sips Installation manual
- Must follow the Steel Stud Manufacturers Association, ICC ES report ESR 3064P

# M-SIPs Roof Panel – Specifications (Insulation type Polyiso)

- R24 4.80" x 45" x 18'
- R38 6.81" x 45" x 18'
- R48 8.54" x 45" x 18'

Panel length: on request up to 39'

### Fire-resistance Assemblies:

- To be determined 1st quarter 2020 in accordance with ASTM E119
- Polyiso insulation, Class A fire rated in accordance with ASTM E 84
- M4 sheathing is Non Combustible according ASTM E 136

The building code definition of an approved thermal barrier is one which is equal in fire resistance to 12.7 mm (1/2 inch) gypsum board. All building codes require an approved thermal barrier on the habitable side of a structure between the interior of the structure and the polyurethane foam.

#### M-Thermo-Panel

If extended R value is demanded the M-Thermo Panel can be applied as continuous insulation, range: R6 - R19.